ADDENDUM NO. 1

WATER MAIN PROJECT 701204
SPEC. NO. 04-126
IN FOLSOM FROM W. PROSPECTOR TO W. PIONEERS

TO ALL PROSPECTIVE BIDDERS:

1. Please Remove Bid Proposal Pages 2 thru 5 and replace with the attached Revised Bid Proposal Pages 2 thru 5.

2. On Page 6 of the Contract Agreement No. 13 should read **'This Project is not tax exempt'.**

3. On Page 25 of the Special Provisions - "Removal of Unsuitable Material" section - **Delete this Section**.

NOTE: Bidders are instructed to sign and fax this page of Addendum No. 1 back to the City of Lincoln Engineering Services, attention Mary Lowe at fax number 402-441-6576, as evidence that this Addendum No. 1 has been received and also staple this page to the front cover of your bid proposal book. Failure to do so could result in rejection of your bid.

_____

Company/Contact Person

Date: 04-21-04
Revised: 05-07-04

Schedule of Items

Contract ID: 701204 Project(s):
Letting Date: 05-12-04 Call Order: 001

Bidder:

Line No.	Item Description	Approx. Quantity and Units	Unit Price Dollars	Unit Price Cts	Bid Amount Dollars	Bid Amount Ct
Section 0001						
	Alt Group					
0005	24.6999 Mobilization	1.000 L.S.				
0010	50.0153 Traffic Control for Construction	1.000 L.S.				
0015	50.0015 Misc. Construction Staking	1.000 L.S.				
0020	23.0005 16" Water Main	5,049.000 L.F.				
0025	23.0006 12" Water Main	470.000 L.F.				
0030	23.0007 8" Water Main	5.000 L.F.				
0035	23.0008 6" Water Main	100.000 L.F.				
0040	22.0850 4" Pipe Sewer Service	800.000 L.F.				
0045	20.0670 30" Smooth Steel Casing, 0.500" Thick, Bored In Place	148.000 L.F.				

Date: 04-21-04
Revised: 05-07-04

Schedule of Items

Contract ID: 701204 Project(s):
Letting Date: 05-12-04 Call Order: 001

Bidder:

Line No.	Item Description	Approx. Quantity and Units	Unit Price Dollars	Unit Price Cts	Bid Amount Dollars	Bid Amount Ct
0050	20.0194 Boring for 16" Water Main	711.000 L.F.				
0055	23.0420 16" Butterfly Valve, M.J.	8.000 Ea.				
0060	23.0430 12" Butterfly Valve, M.J.	2.000 Ea.				
0065	23.0450 8" Gate Valve, M.J.	1.000 Ea.				
0070	23.0460 6" Gate Valve, M.J.	1.000 Ea.				
0075	23.0646 16" Solid Sleeve, M.J. (L=15")	1.000 Ea.				
0080	23.0574 16" X 12" Tee, M.J.	1.000 Ea.				
0085	23.0576 16" X 6" Tee, M.J.	14.000 Ea.				
0090	23.0622 16" X 6" Reducer, M.J.	1.000 Ea.				
0095	23.0658 16" Plug, M.J.	1.000 Ea.				

Date: 04-21-04
Revised: 05-07-04

Schedule of Items

Contract ID: 701204 Project(s):
Letting Date: 05-12-04 Call Order: 001

Bidder:

Line No.	Item Description	Approx. Quantity and Units	Unit Price Dollars	Unit Price Cts	Bid Amount Dollars	Bid Amount Ct
0100	23.0579 12" x 8" Tee, M.J.	1.000 Ea.				
0105	23.0580 12" X 6" Tee, M.J.	1.000 Ea.				
0110	23.0624 12" X 6" Reducer, M.J.	1.000 Ea.				
0115	23.0661 8" Plug, M.J.	1.000 Ea.				
0120	23.0582 6" X 6" Tee, M.J.	1.000 Ea.				
0125	23.0546 6" X 45 Deg. Bend, M.J.	2.000 Ea.				
0130	23.0662 6" Plug, M.J.	1.000 Ea.				
0135	23.0490 Hydrant, Complete L=5.5'	1.000 Ea.				
0140	23.0492 Hydrant, Complete L=6.5'	15.000 Ea.				
0145	23.0665 Conc. for Thrust Blocks & Anchorages (In Place)	20.800 C.Y.				

Date: 04-21-04
Revised: 05-07-04

Schedule of Items

Contract ID: 701204 Project(s):
Letting Date: 05-12-04 Call Order: 001

Bidder:

Line No.	Item Description	Approx. Quantity and Units	Unit Price Dollars	Unit Price Cts	Bid Amount Dollars	Bid Amount Ct
0150	23.0670 Reinf. Stl. for Thrust Blks & Anchorages	749.900 Lb.				
0155	30.0070 Seeding, Type "C"	1.740 Ac.				
0160	02.0010 General Clearing & Grubbing	1.000 L.S.				
	Section 0001 Total					
	Bid Total					