



NOTES: THE CONTRACTOR MAY SUBSTITUTE OTHER DESIGNS FOR EXPANSION AND CONTRACTION JOINT SUPPORTS IN LIEU OF THE TYPE SHOWN WITH PRIOR WRITTEN APPROVAL BY THE ENGINEER.

ALL JOINTS SHALL BE SEALED WITH JOINT SEALING FILLER (HOT POURED TYPE) AS PER STANDARD SPECIFICATIONS.

TIE BARS SHALL BE DEFORMED BARS.

ALL BARS SHALL SATISFY THE BEND TEST REQUIREMENTS FOR STRUCTURAL GRADE BILLET STEEL IN ACCORDANCE WITH THE SPECIFICATIONS.

THE CONTRACTOR MAY USE A MACHINE FOR PLACING THE LONGITUDINAL TIE BARS IN LIEU OF THE TIE BAR PINS. IF A MECHANICAL TIE BAR PLACEMENT MACHINE IS NOT USED, TIE BAR PINS AS SHOWN WILL BE USED.

REVISIONS			CONCRETE ALLEY PAVEMENT	
NO.	BY	DATE		
1				
2				
3				
4				
5				
6				
7				
8				
9				
10				

CITY OF LINCOLN, NEBRASKA OFFICE OF THE CITY ENGINEER				
Date: 2-03 / CAW		Scale: None		
No. Sheets		PLAN NO. L.S.P. 630	Sheet No.	