

**ADDENDUM #1
TO SPEC. 07-116**

**ANTELOPE CREEK TRAIL
PHASE 2
OLD CHENEY ROAD TO HIGHWAY 2
STPB-55(154)
CN 12817**

Addendum #1 to Spec. 07-116 for Antelope Creek Trail Phase 2, Old Cheney Road to Highway 2, bids to be opened on Wednesday, April 18, 2007 at 12:00 noon.

Please note the following:

1) The bid item "SEEDING, TYPE A" shall read "SEEDING, TYPE B". A revised bid form is included with this Addendum #1.

All other terms and conditions to remain unchanged.

Dated this 10th day of April, 2007.

Purchasing Department

Tom Kopplin
Assistant Purchasing Agent

LINE NO.	ITEM NO.	DESCRIPTION OF ITEM	QUANTITY	UNIT PRICE	EXTENSION
1	0030.00	Mobilization	1 LS		
2	1009.00	General Clearing and Grubbing	1 LS		
3	1010.01	Earthwork Measured as Embankment (E.Q.)	3,837 CY		
4	1107.00	Remove Walk	154 SY		
5	3016.	5" Concrete Class 47B-3500 Bikeway	12,601 SY		
6		4" Drain Tile	64 LF		
7	4450.15	15" Reinforced Concrete Pipe	131 LF		
8	4450.24	24" Reinforced Concrete Pipe	119 LF		
9		36" Equivalent, Elliptical Reinforced Concrete Pipe	19 LF		
10		54" Equivalent, Elliptical Reinforced Concrete Pipe	6 LF		
11	4460.15	15" Concrete Pipe Flared End Section	16 Ea.		
12	4460.24	24" Concrete Pipe Flared End Section	2 Ea.		
13		36" Equivalent, Elliptical RCP Flared End Section	2 Ea		
14		Remove and Reset 24" Flared End Section	3 Ea		
15		Remove and Reset 54" Eq., Elliptical Flared End Section	1 Ea		
16	6105.02	Rock Riprap, Type B	42 TON		
17	6406.00	Pipe Railing Fence w/Rub Rail	128 LF		
18	7321.01	Type A Sign	29 EA		
19	9173.20	Subgrade Preparation	15,114 SY		
20		Subgrade Stabilization	60 SY		
21	9185.50	Milling Concrete Curb	144 LF		
22	L001.01	Seeding, Type "B"	5.2 Ac		
23	L022.10	Fabric Silt Fence	2,063 LF		
24		Triangular Silt Barrier	19.5 LF		
25		Earthwork Excavation (for info only)	2520 CY	NA	NA
ESTIMATE TOTAL					

Company Name: _____

Signature: _____ Date: _____