PROFESSIONAL CIVIL ENGINEER
KENT E. EVANS
E-9875
5/07/07
STATE OF NEBRASKA

City of Lincoln, Nebraska
2007
ADDENDUM #1
TO SPEC. 07-146

May 7, 2007
Paving Project No. 701662
27th Street – Pine Lake Road to Yankee Hill Road

Bid opening date remains the same, Wednesday, May 9, 2007.

All addendums shall be signed and attached to the bid document submitted, as noted in Section II. Proposal Requirements and Conditions, Item K. Addendum, in the City of Lincoln Standard Specifications for Municipal Construction.

TO ALL PROSPECTIVE BIDDERS:
The quantities and special provisions for the above referenced project are hereby amended to include the following items:

See Attached

All other terms and conditions remain unchanged.

Dated this 7th day of May, 2007.

Purchasing Department,

Vince Mejer
Purchasing Agent

_____
Signed Acknowledgement

PROFESSIONAL CIVIL ENGINEER
FRED A. BECK
E-6777
05/07
STATE OF NEBRASKA

ADDENDUM NO. 1

SOUTH 27TH STREET – PINE LAKE ROAD TO YANKEE HILL ROAD
PROJECT #701662A
May 7, 2007

1. Refer to Sheet Q-1; Summary of Quantities, Paving Items

   Revise the quantities as follows:
   - Add Item 50.0035, "Temporary Asphalt Pavement"; 400.00 Ton.

2. Refer to Sheet Q-2; Summary of Quantities, Traffic Signal and Lighting Items

   Revise the quantities as follows:
   - Item 24.1508, "Install Luminaire, 250 W HPSV-PC" shall be changed from 43 Each to 9 Each.
   - Add Item 50.0001, "Install Luminaire, 250W HPSV-PC, (Grey Shoebox); 34 Each.
   - Item 24.1194, "Vehicle, Detector Type MD-1" shall be changed from 7 Each to 3 Each.
   - Add Item 24.1196, "Magnetic Vehicle Detector, less probe"; 4 Each.
   - Delete Item 24.6012, "Install Cabinet, Type C & Pad"; 1 Each.
   - Add Item 24.6004, " Install Cabinet, Type C; 1 Each.

3. Refer to the Special Provisions

   Add the following Special Provision.

INSTALL LUMINAIRE 250W HPSV-PC (GREY SHOEBOX)

The Contractor shall install General Electric, DSME 25 S3 M2 GMC 3 GR grey shoebox luminaire or approved equal. Luminaire shall be provided by Lincoln Electric System.

All materials and installation methods shall comply with section 24.23 of the 2006 City of Lincoln Standard Specifications.

Luminaires of the type and wattage required by the plans, complete, in place and accepted by the Engineer, will be measured for payment as single units, and shall be paid for at the contract unit price bid per each item. This price shall be full compensation for furnishing all materials not furnished by the City, all labor, equipment, tools, materials, and incidentals required to complete the work.

4. Refer to the Special Provisions, Construction Phasing

   Revise the 3rd bullet item to modify the unit price for temporary asphalt and for additional asphalt from $30 per ton to $40 per ton.

5. Refer to the Bidding Schedule

   The original bidding schedule shall be considered null and void and shall be replaced with the attached bidding schedule.

6. Any plan sheet revision due to this addendum shall be submitted to the successful bidder.

PROFESSIONAL CIVIL ENGINEER
FRED A. BECK
E-6777
STATE OF NEBRASKA

City of Lincoln

Project Item Schedule

701662

Description: SOUTH 27TH STREET, PINE LAKE ROAD TO YANKEE HILL ROAD- PACKAGE 3 04-11-2007

Location:

Work Type: STORM SEWER

Road Type: RESIDENTIAL

Bid opening Date: 05/09/2007 AT 12:00 pm.

Project Items

Item Number		Quantity	Unit	Unit Price	Extension
	Section: 1 Paving Items				
01.0100	Pavt & Sidewalk Rem	3,767.000	CY	$	$
01.0170	Adj MH to Grade, Cmpl	2.000	EA	$	$
01.0190	Std Monument Box (In Place)	6.000	DMI	$	$
01.0210	Ty "A" Sawing	66.000	LF	$	$
01.0220	Ty "B" Sawing	746.000	LF	$	$
01.0230	Ty "C" Sawing	25.000	LF	$	$
02.0105	Overexcavation	7,467.000	CY	$	$
02.0110	Earth Borrow Measured in Embankment (E.Q.)	33,999.000	CY	$	$

Item Number	Quantity	Unit	Unit Price	Extension
06.0020	118.000	LF	$	$
Combined Curb & Gutter				
06.0050	13.000	EA	$	$
Conc Median Nose, (In Place)				
06.0060	16,132.000	SF	$	$
4" Conc Median Surfacing				
07.0020	41,575.000	SF	$	$
4" Conc Sidewalk				
07.0030	743.000	SF	$	$
6" Conc Driveway				
07.0100	216.000	SF	$	$
Build Detectable Warning Panel				
10.0010	245.000	TON	$	$
Crushed Rock Surfacing (In Place)				
50.0040	34,190.000	SY	$	$
9" Doweled Portland Cement Conc. Pav't W/ Integral Curb				
50.0035	400.000	TON	$40.00	$16,000.00
Misc Temporary Asphalt Pavement				
			Section 1 Total:	$
Section: 2 Storm Sewer Items				
21.0080	533.000	LF	$	$
30" RCP Storm Sewer, Cl III				
21.0090	169.000	LF	$	$
24" RCP Storm Sewer, Cl III				
21.0100	845.000	LF	$	$
18" RCP Storm Sewer, Cl III				
21.0110	2,131.000	LF	$	$
15" RCP Storm Sewer, Cl III				

Item Number	Quantity	Unit	Unit Price	Extension
21.0710	1.000	EA	$	$
30" RC FES, w/Grate				
21.0770	17.000	EA	$	$
72" Storm Sewer Inlet (Cmpl)				
21.0780	13.000	EA	$	$
72" Canted Storm Sewer Inlet (Cmpl)				
21.0820	1.000	EA	$	$
Grate Inlet, Ty "F-1" (Cmpl)				
21.0895	13.000	EA	$	$
Storm Sewer MH, 15" - 30" (Cmpl)				
21.0940	4.260	CY	$	$
Conc for Collars, Elbows, Plugs & Hdwls (In Place)				
21.0950	35.000	LBS	$	$
Reinf Steel for Collars, Elbows & Hdwls (In Place)				
21.1050	3.000	EA	$	$
Tap Ex Storm Sewer MH & Replace				
21.1070	3.000	EA	$	$
Tap Ex RCP				
21.1290	34.000	LF	$	$
Rem 24" Storm Sewer Pipe				
21.1310	123.000	LF	$	$
Rem 18" Storm Sewer Pipe				
21.1320	527.000	LF	$	$
Rem 15" Storm Sewer Pipe				
21.1680	7.000	EA	$	$
Rem 15" RC FES				
21.1740	1.000	EA	$	$
Rem Ex Grate Inlet (Cmpl)				

Item Number		Quantity	Unit	Unit Price	Extension
21.1750	Rem Ex Hdwl (Cmpl)	1.000	INTR	$	$
				Section 2 Total:	$
	Section: 3 Pavement Marking & Signing Items				
13.0430	Polyurea Mkg, 4" Y	200.000	LF	$	$
13.0431	Polyurea Mkg, 4" W	6,074.000	LF	$	$
13.0432	Polyurea Mkg, 8" W	1,426.000	LF	$	$
13.0434	Polyurea Mkg, 12" W	328.000	LF	$	$
13.0436	Polyurea Mkg, 24" W	390.000	LF	$	$
13.0532	Rem Paint Mkg, 8"	688.000	LF	$	$
13.0533	Rem Paint Mkg, 12"	174.000	LF	$	$
13.0560	Raised Pavt Markers	51.000	EA	$	$
14.0001	Traffic Sign, < 4 Sq Ft	2.000	EA	$	$
14.0003	Traffic Sign, 4 Sq Ft < 9 Sq Ft	9.000	EA	$	$
14.0007	"U" Channel Sign Posts	72.000	LF	$	$
14.0017	Tubular Marker	12.000	EA	$	$

Item Number		Quantity	Unit	Unit Price	Extension
14.0050	Ground Sleeve	14.000	EA	$	$
50.0001	Remove Tubular Marker	5.000	EA	$	$
				Section 3 Total:	$
	Section: 4 Water Main Items				
23.0005	16" Water Main	3,547.000	LF	$	$
23.0006	12" Water Main	12.000	LF	$	$
23.0007	8" Water Main	257.000	LF	$	$
23.0008	6" Water Main	675.000	LF	$	$
23.0420	16" Butterfly Valve, MJ	6.000	EA	$	$
23.0450	8" Gate Valve, MJ	4.000	EA	$	$
23.0460	6" Gate Valve, MJ	22.000	EA	$	$
23.0490	Hydrant, Cmpl L=5.5'	8.000	EA	$	$
23.0492	Hydrant, Cmpl L=6.5'	8.000	EA	$	$
23.0500	16" Retainer Glands, MJ	14.000	EA	$	$
23.0510	12" Retainer Glands, MJ	2.000	EA	$	$

Item Number		Quantity	Unit	Unit Price	Extension
23.0520	8" Retainer Glands, MJ	11.000	EA	$	$
23.0530	6" Retainer Glands, MJ	4.000	EA	$	$
23.0534	16" X 90 Deg Bend, MJ	2.000	EA	$	$
23.0538	6" X 90 Deg Bend, MJ	1.000	EA	$	$
23.0542	16" X 45 Deg Bend, MJ	4.000	EA	$	$
23.0546	6" X 45 Deg Bend, MJ	1.000	EA	$	$
23.0574	16" X 12" Tee, MJ	1.000	EA	$	$
23.0576	16" X 6" Tee, MJ	2.000	EA	$	$
23.0583	8" X 6" Tee, MJ	1.000	EA	$	$
23.0586	16" X 6" Swivel Tee, MJ	1.000	EA	$	$
23.0592	6" Anchoring Elbow, MJ	8.000	EA	$	$
23.0594	6" Anchoring Coupling, MJ (L=18")	15.000	EA	$	$
23.0608	16" X 6" Cross, MJ	5.000	EA	$	$
23.0634	8" Offset, 24" Drop, MJ	2.000	EA	$	$

Item Number	Quantity	Unit	Unit Price	Extension
23.0646	1.000	EA	$	$
16" Solid Sleeve, MJ (L=15")				
23.0648	1.000	EA	$	$
12" Solid Sleeve, MJ (L=12")				
23.0649	3.000	EA	$	$
8" Solid Sleeve, MJ (L=12")				
23.0661	1.000	EA	$	$
8" Plug, MJ				
23.0665	9.500	CY	$	$
Conc for Thrust Blocks & Anchorages (In Place)				
23.0670	429.300	LBS	$	$
Reinf Stl for Thrust Blks & Anchorages				
23.0685	1.000	EA	$	$
Reconstruct Water Service				
23.0710	48.000	LF	$	$
1" Copper Water Service Pipe				
23.0920	49.000	LF	$	$
Rem 16" Water Main				
23.0930	20.000	LF	$	$
Rem 12" Water Main				
23.0960	3.000	EA	$	$
Rem & Salvage Hydrant (Cmpl)				
23.1110	5.000	EA	$	$
Rem Plug				
23.1150	1.000	EA	$	$
Rem Reducer				
50.0001	1.000	EA	$	$
16" X 8" Cross, M.J.				

Item Number	Quantity	Unit	Unit Price	Extension
50.0001	1.000	EA	$	$
Remove & Salvage Butterfly Valve				
50.0001	2.000	EA	$	$
16" X 8" Tee, M.J.				
			Section 4 Total:	$
Section: 6 Erosion Control Items				
30.0010	5,677.000	SF	$	$
Sodding, Cmpl				
30.0050	3.840	AC	$	$
Seeding, Ty "B"				
31.0001	998.000	CY	$	$
Topsoil				
32.0040	3,667.000	LF	$	$
Synthetic Fabric Silt Fence Inst				
32.0050	3,667.000	LF	$	$
Synthetic Fabric Silt Fence Maint				
32.0060	3,636.000	LF	$	$
Synthetic Fabric Silt Fence Rem				
32.0070	1.000	EA	$	$
Inst Storm Drain Inlet Protection				
32.0080	1.000	EA	$	$
Storm Drain Inlet Protection Maint				
32.0090	1.000	EA	$	$
Rem Storm Drain Inlet Protection				
50.0001	30.000	EA	$	$
Type III Curb Inlet Filters				
50.0020	0.610	AC	$	$
Cover Crop Seeding				

Item Number		Quantity	Unit	Unit Price	Extension
50.0045	Misc Turf Reinforcement	11,770.000	SF	$	$
				Section 6 Total:	$
	Section: 7 Traffic Signal & Lighting Items				
24.0102	Rem SL, Cmpl	1.000	EA	$	$
24.0105	Rem PB	1.000	EA	$	$
24.0110	Rem Cable	645.000	LF	$	$
24.0807	PB-9	27.000	EA	$	$
24.0810	PB-FOR27	17.000	EA	$	$
24.0895	Conduit, 2" B	62.000	LF	$	$
24.0899	Conduit, 4" B	1,103.000	LF	$	$
24.0900	Conduit, 1/2" T	230.000	LF	$	$
24.0903	Conduit, 1 1/2" T	4,484.000	LF	$	$
24.0904	Conduit, 2" T	3,036.000	LF	$	$
24.0905	Conduit, 3" T	87.000	LF	$	$
24.0906	Conduit, 4" T	3,811.000	LF	$	$

Item Number		Quantity	Unit	Unit Price	Extension
24.0912	Cable, Coaxial	98.000	LF	$	$
24.0991	Cable, Camera Control	196.000	LF	$	$
24.0992	Cable, Emergency Detector	135.000	LF	$	$
24.0994	Cable, Camera Detector	493.000	LF	$	$
24.0995	Cable, Camera Power	98.000	LF	$	$
24.1001	Cable, 2/C TS	1,544.000	LF	$	$
24.1002	Cable, 3/C TS	493.000	LF	$	$
24.1005	Cable, 7/C TS	236.000	LF	$	$
24.1016	Cable, 16/C TS	493.000	LF	$	$
24.1035	Fiber, 12 SM	4,342.000	LF	$	$
24.1040	Cable, Lead-In	4,654.000	LF	$	$
24.1050	Tracer Wire	9,804.000	LF	$	$
24.1054	Cable, No 6 Service	1,956.000	LF	$	$
24.1064	Cable, No 6 CG	2,248.000	LF	$	$

Item Number		Quantity	Unit	Unit Price	Extension
24.1065	Cable, No 8 CG	4,927.000	LF	$	$
24.1072	Cable, No 4 SL	4,496.000	LF	$	$
24.1073	Cable, No 6 SL	9,432.000	LF	$	$
24.1194	Detector, Vehicle Magnetic	3.000	EA	$	$
24.1380	Ground Rod, 10'	14.000	EA	$	$
24.1458	SL Pole, SL-A-C-40-12T-5	5.000	EA	$	$
24.1508	Luminaire, 250W HPSV-PC	9.000	EA	$	$
24.1690	Detector, Vehicle 4 Turns	4.000	EA	$	$
24.1692	Detector, Vehicle 4 Turns UC	27.000	EA	$	$
24.5242	Inst. MA Pole, MA-2 to 26'	2.000	EA	$	$
24.5243	Inst MA Pole, MA-2 > 46'	2.000	EA	$	$
24.5247	Inst MA Pole, MA-2 > 46' less MA	2.000	EA	$	$
24.5248	Inst MA Pole, MA-2 to 46' with Twin Lum less MA	1.000	EA	$	$
24.5249	Inst MA Pole, MA-2 > 46' with Twin Lum less MA	1.000	EA	$	$

Item Number		Quantity	Unit	Unit Price	Extension
24.5801	Inst TS, TS-1, T31	4.000	EA	$	$
24.5803	Inst TS, TS-1, T36	8.000	EA	$	$
24.5822	Inst PS, PS-1, T13C	8.000	EA	$	$
24.6007	Inst Cabinet, F	1.000	EA	$	$
24.6020	Locate Stick	3.000	Ea.	$	$
24.6101	Install Pedestrian Push Button Type PPB LT/RT Arrow	8.000	EA	$	$
24.6199	Inst and Adj Detector Camera	4.000	EA	$	$
24.6201	Inst Metro Street Name Sign	4.000	EA	$	$
24.6204	Inst and Adj Emergency Receiver	1.000	EA	$	$
24.6206	Inst Traffic Monitoring Camera	1.000	EA	$	$
24.6208	Radio Antenna Hardware	1.000	EA	$	$
50.0001	Street Light Pole, Type SL-A-35-3S-0 (Grey Shoebox)	15.000	EA	$	$
50.0001	Street Light Pole, Type SL-A-45-3S-0 (Grey Shoebox)	10.000	EA	$	$
50.0001	Street Light Pole, Type SL-A-50-3S-0 (Grey Shoebox)	3.000	EA	$	$

Item Number	Quantity	Unit	Unit Price	Extension
50.0001	1.000	EA	$	$
Remove Detector, Vehicle Magnetic				
50.0001	34.000	EA	$	$
Misc Install Luminaire, 250W HPSV-PC, (Grey Shoebox)				
24.1196	4.000	EA	$	$
Magnetic Vehicle Detector less Probe				
24.6004	1.000	EA	$	$
Inst Cabinet, C				
			Section 7 Total:	$
Section: 8 Miscellaneous Items				
0.2000	1.000	LS	$	$
Const Staking				
0.4000	1.000	LS	$	$
Mobilization 10% of Total cost				
01.0200	3.000	EA	$	$
Std Dead End Barricade, Ty III, (In Place)				
02.0010	1.000	LS	$	$
Gen Clearing & Grubbing				
09.0070	448.000	LF	$	$
48" Pipe Railing Fence (In Place)				
15.0001	1.000	LS	$	$
Traffic Ctrl for Const				
50.0045	3,480.000	SF	$	$
Special Modular Block Retaining Wall				
			Section 8 Total:	$
			Estimate Total:	$