ADDENDUM NO. 1

STORM SEWER PROJECT 702193
BEING AT 45TH AND GINNY
SPEC. NO. 07-159

PROFESSIONAL CIVIL ENGINEER
HOLLY S. LIONBERGER
E-10660
05/17/2007
STATE OF NEBRASKA

TO ALL PROSPECTIVE BIDDERS:

The following questions/clarifications have been received:

1. Q: Can a contractor construct the entire project in 2008?
   A: Phase I needs to be complete in 2007, with Phase II to follow in 2008 to coordinate with the Pound Middle School renovations.

2. Q: Plan note 3 states see Special Provisions for maintaining access to homes. The Special Provisions do not state anything to that effect. Does this mean we can close the road completely with no worry of access?
   A: Access to adjacent properties shall be as covered in the City of Lincoln Standard Specifications for Municipal Construction, Chapter 15 - Traffic Control, Section 15.06 Access to Adjacent Properties.

3. Q: There is not a pay item for Truncated Domes. Should there be? Or are they subsidiary to the sidewalk?
   A: A bid item has been added for BUILD DETECTABLE WARNING PANEL – 88 SF. Please replace original bid form with bid form attached with this addendum.

Please sign and fax this cover sheet to Mary Lowe in Engineering Services at (402)441-6576 as receipt of receiving this Addendum, failure to do so could result in your bid being rejected.

_____

Contractor

City of Lincoln

Project Item Schedule

702193

Description: 45th and Ginny Storm Sewer Project
Location: 45th and Ginny
Work Type: STORM SEWER
Road Type: RESIDENTIAL
Bid opening Date: 05/16/2007 AT 12:00 pm.

Project Items

Item Number		Quantity	Unit	Unit Price	Extension
	Section: 1 General Provisions & Requirements				
0.2000	Const Staking	1.000	LS	$	$
0.4000	Mobilization	1.000	LS	$	$
				Section 1 Total:	$
	Section: 2 Pavement Construction & Reconstruction				
01.0100	Pavt & Sidewalk Rem	1,170.000	CY	$	$
01.0130	5" Conc Base	4,195.000	SY	$	$
01.0151	AC Surface Course, For Non-Art	603.000	TON	$	$
01.0170	Adj MH to Grade, Cmpl	1.000	EA	$	$
01.0210	Ty "A" Sawing	1,903.000	LF	$	$
				Section 2 Total:	$
	Section: 3 Eathwork				

Item Number		Quantity	Unit	Unit Price	Extension
02.0010	Gen Clearing & Grubbing	1.000	LS	$	$
02.0020	Tree Rem (12" to 23")	3.000	EA	$	$
				Section 3 Total:	$
	Section: 4 Portland Cement Concrete Curb & Median Construction				
06.0020	Combined Curb & Gutter	2,890.000	LF	$	$
				Section 4 Total:	$
	Section: 5 Sidewalks and Driveways				
07.0020	4" Conc Sidewalk	2,495.000	SF	$	$
07.0040	5" Conc Driveway	5,473.000	SF	$	$
07.0100	Build Detectable Warning Panel	88.000	SF	$	$
				Section 5 Total:	$
	Section: 6 Traffic Pavement Marking				
15.0001	Traffic Ctrl for Const	1.000	LS	$	$
				Section 6 Total:	$
	Section: 7 Storm Drainage Items				
21.0100	18" RCP Storm Sewer, Cl III	38.000	LF	$	$
21.0110	15" RCP Storm Sewer, Cl III	137.000	LF	$	$
21.0150	60" RCP Storm Sewer, Cl IV	179.000	LF	$	$

Item Number	Quantity	Unit	Unit Price	Extension
21.0160	46.000	LF	$	$
54" RCP Storm Sewer, Cl IV				
21.0170	2,148.000	LF	$	$
48" RCP Storm Sewer, Cl IV				
21.0180	43.000	LF	$	$
42" RCP Storm Sewer, Cl IV				
21.0190	117.000	LF	$	$
36" RCP Storm Sewer, Cl IV				
21.0200	294.000	LF	$	$
30" RCP Storm Sewer, Cl IV				
21.0780	12.000	EA	$	$
72" Canted Storm Sewer Inlet (Cmpl)				
21.0850	1.000	EA	$	$
Grate Inlet, Ty "H" (Cmpl)				
21.0880	3.000	EA	$	$
Storm Sewer MH, 42"-48" (Cmpl)				
21.0885	2.000	EA	$	$
Storm Sewer MH, 42" (Cmpl)				
21.0920	42.000	CY	$	$
Conc for Structures (In Place)				
21.0930	3,780.000	LBS	$	$
Reinf Steel for Structures (In Place)				
21.0940	13.000	CY	$	$
Conc for Collars, Elbows & Hdwls (In Place)				
21.0950	1,105.000	LBS	$	$
Reinf Steel for Collars, Elbows & Hdwls (In Place)				
21.1070	2.000	EA	$	$
Tap Ex RCP				

Item Number	Quantity	Unit	Unit Price	Extension
21.1230	185.000	LF	$	$
Rem 60" Storm Sewer Pipe				
21.1240	56.000	LF	$	$
Rem 54" Storm Sewer Pipe				
21.1280	106.000	LF	$	$
Rem 30" Storm Sewer Pipe				
21.1290	27.000	LF	$	$
Rem 24" Storm Sewer Pipe				
21.1310	79.000	LF	$	$
Rem 18" Storm Sewer Pipe				
21.1320	107.000	LF	$	$
Rem 15" Storm Sewer Pipe				
21.1325	6.000	LF	$	$
Rem 12" Storm Sewer Pipe				
21.1710	4.000	EA	$	$
Rem Ex Inlet (Cmpl)				
21.2090	92.000	SY	$	$
Geotextile Filter Fabric (In Place)				
21.2111	58.000	TON	$	$
Rip-Rap (In Place)				
			Section 7 Total:	$
Section: 8 Sanitary Sewers				
22.0820	10.000	EA	$	$
Reconstruct Sanitary Sewer Service				
22.0850	200.000	LF	$	$
4" Pipe Sewer Service				
			Section 8 Total:	$
Section: 9 Water Mains				

Item Number	Quantity	Unit	Unit Price	Extension
23.0008	200.000	LF	$	$
6" Water Main				
23.0530	48.000	EA	$	$
6" Retainer Glands, MJ				
23.0546	16.000	EA	$	$
6" X 45 Deg Bend, MJ				
23.0650	8.000	EA	$	$
6" Solid Sleeve, MJ (L=12")				
23.0654	6.000	EA	$	$
6" Dual Purpose Sleeve, MJ (L=12")				
23.0665	9.000	CY	$	$
Conc for Thrust Blocks & Anchorages (In Place)				
23.0670	272.000	LBS	$	$
Reinf Stl for Thrust Blks & Anchorages				
23.0680	10.000	EA	$	$
Construct Water Service				
23.0695	100.000	LF	$	$
2" Copper Water Service Pipe				
23.0710	100.000	LF	$	$
1" Copper Water Service Pipe				
23.0950	180.000	LF	$	$
Rem 6" Water Main				
			Section 9 Total:	$
Section: 10 Seeding and Sodding				
30.0010	19,000.000	SF	$	$
Sodding, Cmpl				
30.0050	0.700	AC	$	$
Seeding, Ty "B"				
			Section 10 Total:	$

Item Number	Quantity	Unit	Unit Price	Extension
Section: 11 Erosion Control				
32.0040 Synthetic Fabric Silt Fence Inst	115.000	LF	$	$
32.0070 Inst Storm Drain Inlet Protection	32.000	EA	$	$
			Section 11 Total:	$
Section: 12 Miscellaneous				
50.0001 Misc Remove Outlet Structure	1.000	EA	$	$
50.0001 Misc Plug Storm Sewer	7.000	EA	$	$
50.0005 Misc 12" RCP Storm Sewer, Cl III	6.000	LF	$	$
99.0501 72" Power Grinder	4.500	HRS	$	$
99.0502 16" Power Grinder	2.000	HRS	$	$
99.0504 Power Broom	11.000	HRS	$	$
99.0505 Power Flusher	2.000	HRS	$	$
99.0507 10 Cubic Yard Dump Truck	19.000	HRS	$	$
99.0508 1/2 Cubic Yard Front-End Loader	9.000	HRS	$	$
99.0509 3 Cubic Yard Front-End Loader	2.000	HRS	$	$

Item Number	Quantity	Unit	Unit Price	Extension
99.0510 Air Compressor	2.000	HRS	$	$
			Section 12 Total:	$
			Estimate Total:	$

Company Name: _____

Signature: _____ **Date:** _____