

**LINCOLN CITY/LANCASTER COUNTY PLANNING STAFF REPORT**

**for MAY 12, 2004 PLANNING COMMISSION MEETING**

**P.A.S.:** Preliminary Plat #01012, West Park 2<sup>nd</sup> Addition

**PROPOSAL:** To preliminary plat 19 residential lots and one lot for an early childhood care facility.

**LOCATION:** S. W. 15<sup>th</sup> Ct. & West "A" St.

**WAIVER REQUEST:**

1. Lot depth to be less than 120' for lots that back on to West "A" St.
2. Improvements to urban standards for West "A" St.
3. Sanitary sewer running opposite street grades in West "B" Ct.
4. Turnaround meeting design standards in West "B" Ct.
5. The connection of West "B" Ct. to West "B" St.

**LAND AREA:** 5.4 acres, more or less.

**CONCLUSION:** With conditions the proposal is in conformance with the Comprehensive Plan, Zoning and Subdivision Ordinances.

**RECOMMENDATION:**

Preliminary Plat Conditional Approval

**WAIVERS**

- |   |          |
|---|----------|
| 1. Lot depth to be less than 120' for lots that back on to West "A" St. | Approval |
| 2. Improvements to urban standards for West "A" St.                     | Approval |
| 3. Sanitary sewer running opposite street grades in West "B" Ct.        | Approval |
| 4. Turnaround meeting design standards in West "B" Ct.                  | Approval |
| 5. Connection of West "B" Ct. to West "B" St.                           | Approval |

**GENERAL INFORMATION:**

**LEGAL DESCRIPTION:** Lots 1-14, Outlot "A" and Outlot "B", West Park Addition, located in the SE 1/4 of Section 28, Township 10 North, Range 6 East, Lincoln, Lancaster County, Nebraska.

**EXISTING ZONING:** R-3 with Community Unit Plan

**EXISTING LAND USE:** Residential and daycare facility.

**SURROUNDING LAND USE AND ZONING:**

North:	R-2 Residential	Right-of-way for Homestead Expressway
South:	R-2 Residential	Single family residential
East:	R-2 Residential	Single family residential and church
West:	R-2 Residential	Single family residential and undeveloped

**ASSOCIATED APPLICATIONS:** Special Permit 1726B

**COMPREHENSIVE PLAN SPECIFICATIONS:**

Maximize the community's present infrastructure investment by planning for residential and commercial development in areas with available capacity. This can be accomplished in many ways including encouraging appropriate new development on unused land in older neighborhoods and encouraging a greater amount of commercial space per acre and more dwelling units per acre in new neighborhoods." (F-17)

"Encourage different housing types and choices, including affordable housing, throughout each neighborhood for an increasingly diverse population." (F-18)

"Interconnected networks of streets, trails, and sidewalks should be designed to encourage walking and bicycling, reduce the number and length of automobile trips, conserve energy and for the convenience of the residents." (F-18)

The Land Use Plan identifies this area as urban residential. (F-25)

Guiding principles for new neighborhoods includes:

1. Similar housing types face each other: single family faces single family, change to different use at rear of lot;
2. Parks and open space within walking distance to a ll residences;
3. Pedestrian orientation; shorter block lengths, sidewalks on both sides of all roads ( F-67)

The Plan thus commits Lincoln and Lancaster County to preserve unique and sensitive habitats and endorses creative integration of natural systems into developments. (F-51)

Wetlands provide distinctive habitat opportunities for various plants and animals, as well as offering flood control and water filtration benefits. (F-54)

**HISTORY:**

Date when preliminary plat was submitted:	July 12, 2001
Date when Planning Director's letter was sent:	August 13, 2001

Date when revised preliminary plat was submitted: April 7, 2004

**March 15, 1999** Special Permit #1726A to amend the community unit plan to allow a day care facility and 10 additional dwelling units was approved by City Council.

**February 10, 1999** Final Plat #98032, West Park Addition, was approved by Planning Commission.

**September 14, 1998** Special Permit #1726 for a community unit plan for 13 dwelling units was approved by City Council.

**September 14, 1998** Preliminary Plat #98013 was approved by City Council

**UTILITIES:** All utilities are available to serve this development.

**TRAFFIC ANALYSIS:** West "A" St. is classified as a minor arterial. There are no projects proposed for West "A" St. abutting this plat in the 2025 Comprehensive Plan. West "A" St. is classified as a minor arterial. There are no projects proposed for West "A" St. abutting this plat in the 2025 Comprehensive Plan. The lots will take access from West "B" Ct., a private roadway. A waiver has been requested with the preliminary plat requiring that West "B" Ct. connect to West "B" St. A connection of the two streets would require development in the wetlands.

**PUBLIC SERVICE:** The nearest fire station is located on Coddington Ave. just south of West "A" St.  
The nearest elementary school is Roper Elementary located at West South St. & Coddington Ave.

**ENVIRONMENTAL CONCERNS:**

The proposed development is within the limits of existing wetlands. The applicant is mitigating the loss of wetlands. The applicant has received a Section 404 permit from the Army Corps of Engineers.

The applicant has submitted a mitigation plan. A conservation easement should be placed over the mitigation areas.

The site contains freshwater wetlands on saline soils, classified as Category III wetlands. A conservation easement has been placed over the wetlands and the wetlands have been placed on an outlot.

**ANALYSIS:**

1. This request is to preliminary plat 20 lots, 19 lots for residential and one lot for a early childhood care facility. Thirteen of the residential lots and the day care lot were previously platted.
2. The applicant is requesting a waiver for lot depth to be less than 120' for lots backing onto West "A" St. The Planning Department does not object to this waiver. This waiver would allow the new dwellings to be in line with the existing dwellings.
3. The applicant is requesting a waiver to improvements along West "A" St. The preliminary plat for West Park 1<sup>st</sup> Addition granted a waiver to requiring curb and gutters along West "A" St. The Planning Department does not object to this waiver.
4. The waiver request to the design standards for permanent turnarounds on West "B" Ct. is acceptable to Planning Department. Fifteen dwelling units will take access from West "B" Ct. A cul-de-sac meeting design standards would require construction within the mitigated wetlands area.

**CONDITIONS:**

Site Specific:

1. After the subdivider completes the following instructions and submits the documents and plans and 6 copies to the Planning Department office, the preliminary plat will be signed by the Chair of the Planning Commission certifying approval: (NOTE: These documents and plans are required by ordinance or design standards.)
  - 1.1 Revise the preliminary plat to show:
    - 1.1.1 Correct note 7 to change "West Park Court" to "West B Ct."
    - 1.1.2 Add the following note: "The conversion plan for the early childhood care facility allows a maximum of 10 dwelling units."
    - 1.1.3 Add to the Requested Waivers a waiver to turnaround meeting City design standards in West "B" Ct.

- 1.1.4 Identify the mitigation areas within the boundaries of a conservation easement.
- 1.1.5 Additional information and revisions regarding grading & drainage and flooding as requested by the Public Works Department.

2. The Planning Commission approves associated request:

- 2.1 A modification to the requirements of the land subdivision ordinance to permit West "B" Ct without a turnaround meeting City design standards, lot depth to be less than 120' for lots that back on to West "A" St., improvements to urban standards for West "A" St. and sanitary sewer running opposite street grades in West "B" Ct.

General:

3. Final Plats will be approved by the Planning Director after:

- 3.1 You have completed or posted a surety to guarantee the completion of the public streets, private roadway improvements, sidewalks, sanitary sewer system, water system, drainage facilities, land preparation and grading, sediment and erosions control measures, storm water detention/retention facilities, drainageway improvements, street lights, landscaping screens, street trees, temporary turnaround and barricades, and street name signs.

3.2. You must agree:

To submit to the Director of Public Works a plan showing proposed measures to control sedimentation and erosion and the proposed method to temporarily stabilize all graded land for approval.

To complete the private improvement shown on the preliminary plat.

To maintain the outlots and private improvements on a permanent and continuous basis. However, the subdivider may be relieved and discharged of this maintenance obligation upon creating in writing a permanent and continuous association of property owners who would be responsible for said permanent and continuous maintenance. The subdivider shall not be relieved of such maintenance obligation until the document or documents creating said property owners association have been reviewed and approved by the City Attorney and filed of record with the Register of Deeds.

To continuously and regularly maintain the street trees along the private roadways and landscape screens.

To submit to the lot buyers and builders a copy of the soil analysis.

To pay all improvement costs.

To comply with the Land Preparation and Grading requirements of the Land Subdivision Ordinance.

To relinquish the right of direct vehicular access from Lots 7-8 to West "A" Street.

To perpetually maintain the sidewalks in the pedestrian way easements at their own cost and expense.

Prepared by:

Tom Cajka, 441-5662, [tcajka@ci.lincoln.ne.us](mailto:tcajka@ci.lincoln.ne.us)  
Planner

**DATE:** April 23, 2004

**APPLICANT:** Kent Thompson  
West Park L.L.C.  
6800 S. 32<sup>nd</sup> St. Suite C  
Lincoln, NE 68516  
(402) 421-7700

**OWNER:** same as applicant

**CONTACT:** Brian D. Carstens  
Brian D. Carstens & Associates  
601 Old Cheney Rd. Suite C  
Lincon, NE 68512  
(402) 434-2424




2002 aerial

# Preliminary Plat #01012 West Park 2nd Add

## Zoning:

- R-1 to R-8 Residential District
- AG Agricultural District
- AGR Agricultural Residential District
- R-C Residential Conservation District
- O-1 Office District
- O-2 Suburban Office District
- O-3 Office Park District
- R-T Residential Transition District
- B-1 Local Business District
- B-2 Planned Neighborhood Business District
- B-3 Commercial District
- B-4 Lincoln Center Business District
- B-5 Planned Regional Business District
- H-1 Interstate Commercial District
- H-2 Highway Business District
- H-3 Highway Commercial District
- H-4 General Commercial District
- I-1 Industrial District
- I-2 Industrial Park District
- I-3 Employment Center District
- P Public Use District

One Square Mile  
Sec. 28 T10N R6E



STATION N 8357' E

29 30

W. B<sup>th</sup> ST.

2 1

HEIGHTS

29 30


OUTLOT B<sup>1</sup>  
NON-BUILDABLE  
OPEN SPACE &  
PASSIVE RECREATION

LIMITS OF EXISTING UTILITIES  
AS PER PLAN SHEET BY TERRACON  
ON FILE

WEST B<sup>1</sup> CT.

WEST A<sup>1</sup> 5TH CT.


WEST A<sup>1</sup> STREET



412.53' 5 09' 34" 24" W

NOT TO SCALE

STATION 10+00 N. 0+1537.7 E



OUTLOT 'B'  
NON-BUILDABLE  
OPEN SPACE &  
PASSIVE RECREATION

UNITS OF EXISTING WALKWAYS  
AS DEMONSTRATED BY TERRAZZO  
ON EAST

EXISTING  
LOT 20  
  
EXISTING  
EARLY  
CHILDHOOD  
CARE FACILITY  
1 - STORY  
10,000 SF.

EXISTING  
LOT 19  
EXISTING  
LOT 18  
EXISTING  
LOT 17  
EXISTING  
LOT 16  
EXISTING  
LOT 15  
EXISTING  
LOT 14  
EXISTING  
LOT 13  
EXISTING  
LOT 12  
EXISTING  
LOT 11  
EXISTING  
LOT 10  
EXISTING  
LOT 9  
EXISTING  
LOT 8  
EXISTING  
LOT 7  
EXISTING  
LOT 6  
EXISTING  
LOT 5  
EXISTING  
LOT 4  
EXISTING  
LOT 3  
EXISTING  
LOT 2  
EXISTING  
LOT 1

HEIGTS

WEST "A" STREET

1/8" = 1'-0"  
20' = 1" = 240'

NOT TO SCALE

# Memorandum

---

<b>To:</b>	Tom Cajka, Planning Department
<b>From:</b>	Chad Blahak, Public Works and Utilities
<b>Subject:</b>	West Park 2nd Addition Preliminary Plat #01012 and Special Permit #1726
<b>Date:</b>	4/22/04
<b>cc:</b>	Randy Hoskins

Engineering Services has reviewed the submitted plans for the West Park 2nd Addition Preliminary Plat and Special Permit, located north of West A Street at SW 15th Street, and has the following comments:

- The grading and drainage plan needs to be revised to reflect the current city storm sewer project in West A Street adjacent to this plat.
- The grading plan shows proposed contours that create low spots in the area north of the proposed and existing buildings that have no positive drainage. The grading plan needs to be revised to show positive drainage for these areas.
- Information needs to be provided showing that Lots 8 and 9 will not be flooded during the 100yr storm.
- A waiver of design standards for permanent turnaround geometry will need to be requested and justification will need to be provided for West B Court.

# Memo



**To:** Tom Cajka, Planning Department

**From:** Mark Canney, Parks & Recreation

**Date:** April 21, 2004

**Re:** West Park 2<sup>nd</sup> Addition

---

Staff members of the Lincoln Parks and Recreation Department have conducted a plan review of the above-referenced application/proposal and have the following comments:

1. While not a requirement, please consider using a Patmore Ash rather than an Emerald Queen Maple. Emerald Queen Maple are subject to sunscald and damage in unprotected sites.
2. Section 26.23.160 of the Land Subdivision Ordinance requires, at the City's discretion, the dedication of suitable park land for neighborhood parks as part of the platting process, paying impact fees with the submission of building permits, or a combination of both. At this time, the Parks Department is requesting impact fees in lieu of park land.


If you have any additional questions, comments or concerns, please feel free to contact me at 441-8248. Thank you.



DEPARTMENT OF THE ARMY  
CORPS OF ENGINEERS, OMAHA DISTRICT  
NEBRASKA REGULATORY OFFICE - KEARNEY  
1430 CENTRAL AVENUE, SUITE 4  
KEARNEY, NEBRASKA 68847-6866

April 5, 2004

Mr. Kent Thompson  
West Lake LLC  
PO Box 6896  
Lincoln, Nebraska 68506-0896



Dear Mr. Thompson:

We have reviewed your request for Department of the Army authorization for the housing development (West Park 2<sup>nd</sup> Addition) in wetlands. The work will be carried out in accordance with plans received on July 6, 2000. The site is located in the SE¼ of Section 28, Township 10 North, Range 6 East, Lancaster County, Nebraska.

Based on the information you provided, this office has determined that your work is authorized by the Department of the Army Nationwide Permit No. 39, found in the January 15, 2002 Federal Register (Vol. 67, No. 10, Part II), Issuance of Nationwide Permits. Enclosed is a fact sheet that fully describes this Nationwide Permit and lists the General Conditions that must be adhered to for this authorization to remain valid.

**This authorization is subject to the following Special Condition(s):**

1. Wetland impacts will be mitigated at a minimum ratio of 1½ acres of created wetland for every 1.0 acre of impacted wetland. Mitigation shall be accomplished as outlined in the March 5, 1999 Mitigation Plan prepared by Terracon, Omaha, Nebraska. Should the mitigation fail to produce the type and level of compensation necessary, the permittee shall comply with the Corps' directives to provide the required mitigation. If the mitigation area is considered to be failing at any time, the permittee shall undertake action, as directed by the Corps of Engineers, to remedy the failure.
2. Buffer strips shall be set aside around perimeter of the mitigation site measuring 30 feet from the outer-most boundary of the mitigation wetland. The buffer strips shall be planted to appropriate perennial, native grasses and forbs and maintained in this condition. Reed Canary Grass (*Phalaris arundinacea*), Purple Loosestrife (*Lythrum salicaria*) and Smooth Brome (*Bromus inermis*) are **NOT** appropriate choices of vegetation. Revegetation will be acceptable when ground cover of desirable species reaches 75%. The permittee shall provide to the Kearney Regulatory Office documentation verifying that the mitigation site was constructed and seeded before May 1, 2004. This documentation may include dates of construction and seeding, planting list, seed bag tags or receipts.

3. Monitoring reports of the wetland mitigation site shall be submitted to the Kearney Regulatory Office to ensure the site is developing properly. The reports shall include, at a minimum, the following: 1) All plant species along with their estimated relative frequency and percent cover; 2) Any fauna noted using the area; 3) Referenced photographs, showing all representative areas of the mitigation site taken at least once each year during the growing season; 4) a set of as-built plans of the mitigation site to see as the baseline for future monitoring. Monitoring reports shall be due November 1 of 2004, 2005 and 2006. If construction is not completed by October 1, 2004, monitoring reports shall be due November 1 of 2005, 2006 and 2007. Please contact the Kearney Regulatory Office if construction is not completed before October 1, 2004 to ensure the proper monitoring schedule.

4. To protect against future impacts on the mitigation site, an appropriate real estate instrument such as a conservation easement or a deed restriction shall be placed on the entire mitigation site and the buffer areas. After the completion of construction, the permittee shall provide to the Kearney Regulatory Office a legal description of the land to be preserved and a draft Covenant of Dedication. A certified copy of the real estate instrument, as recorded with the Lancaster County Registrar of Deeds, shall be submitted to the Kearney Regulatory Office by June 30, 2005.

5. The permittee shall assume all liability for accomplishing corrective work should the Corps of Engineers determine that the compensatory mitigation has not been fully satisfactory. Remedial work may include, but is not limited to, regarding &/or replanting the site. This responsibility shall extend for a period three years upon completion of the work.

6. Measures will be employed prior to filling activity in waters of the US to reduce soil erosion and sedimentation into channels/wetlands. These may include silt curtains, temporary sediment basins, berms, erosion control blankets, turf reinforcement, vertical track walking and grass seeding. The amount of sediment entering channels/wetlands and leaving the site shall be reduced to the maximum extent practicable. If the permittee fails to institute all appropriate measures, the Corps of Engineers reserves the option to halt all earthmoving operations until erosion/sedimentation problems are corrected.

7. Upon completion of the project, all areas disturbed by construction shall be revegetated to appropriate perennial, native grasses and forbs and maintained in this condition. Reed Canary Grass (*Phalaris arundinacea*), Purple Loosestrife (*Lythrum salicaria*) and Smooth Brome (*Bromus inermis*) are NOT appropriate choices of vegetation. The disturbed areas shall be reseeded concurrent with the project or immediately upon completion. Revegetation shall be acceptable when ground cover of desirable species reaches 75%. If this seeding cannot be accomplished by September 15 of the year that grading is completed, then an erosion blanket shall be placed on the disturbed slopes adjacent to the wetlands/channel. The erosion blanket shall remain in place until ground cover of desirable species reaches 75%. If the seeding can be accomplished by September 15, all seeded areas shall be properly mulched to prevent additional erosion.

Although an individual Department of the Army permit will not be required for the project, this does not eliminate the requirement that you obtain any other applicable Federal, state, tribal or local permits as required. Please note that deviations from the original plans and specifications of your project could require additional authorization from this office.

You are responsible for all work accomplished in accordance with the terms and conditions of the Nationwide Permit. If a contractor or other authorized representative will be accomplishing the work authorized by the Nationwide Permit in your behalf, it is strongly recommended that they be provided a copy of this letter and the attached conditions so that they are aware of the limitations of the applicable Nationwide Permit. Any activity that fails to comply with all of the terms and conditions of the Nationwide Permit will be considered unauthorized and subject to appropriate enforcement action.

In compliance with General Condition 14, the attached Compliance Certification form must be signed and returned to the address listed upon completion of the authorized work and any required mitigation.

This verification will be valid until **April 5, 2006**.

Should you at any time become aware that either an endangered and/or threatened species or its critical habitat exists within the project area, you must immediately notify this office.

If you have any questions concerning this determination or jurisdiction, please feel free to contact Mrs. Barb Friskopp at (308) 234-1403 and reference Nationwide Permit No. 04-10274.

Sincerely,



*J* Michael Rabbe  
Nebraska State Program Manager

Enclosures

Copy Furnished:

DEQ (Hickman)  
Brian Carstens & Associates

